

Thermal Products Corporation

ELECTRA-FLOW ELECTRONIC VAV CEILING DIFFUSER

QUICK CHECK LIST

Quick check list is to be used in conjunction with the Trouble Shooting Guide.

Measurements taken at terminals on the REE-4106 relay module.
(Actual measurements are in parenthesis)

1. Supply VAC measured at 9 and C terminals _____
(24 VAC)
2. Output VDC measured at - and + terminals _____
(9 VDC)
3. Output VAC measured at *LOAD* and C terminals with 0 VDC on terminal T: _____
(Zero VAC)
4. Output VAC measured at *LOAD* and C terminals with ≥ 6 VDC on terminal T: _____
24 VAC)
5. Output VAC measured at *LOAD* and C terminals with ≥ 1.5 VDC and ≤ 6 VDC on terminal T: _____
(cycling 24 VAC)

